

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 21,293

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
JUL 11 1980

Operator's Full Name TWIN WESTERN RESOURCES, INC.
Complete Address UNION CENTER BLDG. SUITE 922 - WICHITA NO. 67202
Lease Name HENRY Well No. #2
Location C-SE-NW Sec 23 Twp. 19 Rge. 22(E) (W) W
County NESS Total Depth 4397 FE
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor HELSO CASING PULLING
Address BOX 176 CHASE, MAN'S. 67524 License No. _____
Operation Completed: Hour 12:10 PM Day 10th Month JULY Year 1980

The above well was plugged as follows:

8 5/8" 308^{FE} SP CUC - 5 1/2" SET AT 4287^{FE} w/150^{SE} CNT.
PLUG BACK T.D. 4397^{FE} - PERDS 4363^{FE} TO 4375^{FE}
SAND TO 4325^{FE} AND 5^{SE} SAND AT BOTTOM.
SHOT PIPE (6) TIMES RECOVERED 2591^{FE}
ORDERED 140^{SE} 50^{SE} PORMIX 6% GEL. → 20^{SE} GEL. → 5^{SE} HULL'S → 8 5/8" PLUG.
PUMPED IN WITH PUMP TRUCK. THROUGH 8 5/8" PLUG CONTAINER
PUT IN - 3^{SE} HULL'S → 14^{SE} GEL → 70^{SE} CNT → 6^{SE} GEL → 2^{SE} HULL'S
RELEASE PLUG AND 70^{SE} CNT. - MAX PRESSURE 500^{LB} CEMENTED BY
ALLIED CNT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Marion Schmidt
Well Plugging Supervisor

DATE 7-11-80

INV. NO. 2575-W