

15-135-30217-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1966
3-28-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pains & Williamson Oil Co.

Complete Address: 1425 Wichita Plaza, Wichita Kansas

Lease Name Ficken Well No. 1

Location C-NE-NE Sec. 35 Twp. 19 Rge. 22 (E) (W) ←

County Wess Total Depth 4462

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 10³⁰ P Day 26 Month 3 Year 1966

The Above well was plugged as follows:

RTD 4462' 8 5/8" at 358' (cwc) 1905x.
Canned Pits. Circulated hole w/ dry mud. set cementing
plug at 540ft. Displaced 20 5/8x Cem. thru drill pipe, dry
1" mud to 350 ft, set cementing plug and displaced 20 5/8x Cem.
thru drill pipe, dry mud to 40ft. Built solid bridge of
Cementing Plug 1/2 5/8x hulls & 10 5/8x Cem. to base of Cellar.
Plugged Rat Hole w/ 2 5/8x.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/28/66
INV. NO. 2948-ul

Signed: Leo Massey
Well Plugging Supervisor