

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 435 - 21343 60000 (of this well)

Operator's Full Name THUNDERBIRD DRILLING INC.

Complete Address BOX 18407 - WICHITA, KANS. 67202

Lease Name STEINERT Well No. #1

Location C-NE-SW Sec 31 Twp. 19 Rge. 22 (E) (W) W

County NESS Total Depth 4403 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor HELSO CHASING PULLING

Address BOX 176 CHASE, KANS. 67524 License No. 832

Operation Completed: Hour 11:30 AM Day 30 Month NOV. Year 1979

The above well was plugged as follows:

8 5/8" 278 FT. SD. CUC. W/ 225 ST. COMMON 2% GEL. - 3% CA. - CL.

4 1/2" SET AT. 4393 FT. W/ 70 ST. -> PERFS 10 FT. OPEN HOLE.

BOTTOM SAND TO 4350 FT. AND 4 ST. CMT. - SHOT PIPE SEVERAL TIMES,

RECOVERED 2700 FT. -> ORDERED 140 ST. 50 PBMIX 6% GEL - 20 ST. GEL

4 ST. HULL'S + 8 5/8" PLUG. -> (PUMPED IN 8 5/8" WITH PUMP TRUCK.)

PUT IN -> 2 ST. HULL'S - 12 ST. GEL -> 70 ST. CMT. -> 8 ST. GEL - 2 ST. HULL'S

RELEASED PLUG. AND 70 ST. CMT. -> MAX PRESSURE 500 LBS SHUT IN 50 LBS

CEMENTED BY ALLIED CEMENTING

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-6-79

INV. NO. 1039-W

Signed: [Signature]
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
12-3-79
- 3 1979