

DISTRICT CONSERVATION AGENT'S REPORT

*Handwritten initials and signature*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 124-28

LOCATION NW NW SE

SEC. 21 TWP. 34 SRGE. 5W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease L. R. Bird

Operator The Texas Company Address 614 Bitting Bldg.,  
Wichita, Kansas

Field \_\_\_\_\_ County Harper

Total Depth 4596 Feet.

Plugging Contractor Stickle Drilling Company

Plugging Contractor's License No. Rotary Dry Hole

Address 507 Bitting Bldg., Wichita, Kansas

(Describe briefly the manner in which the well was plugged)

604 feet of 10-3/4" casing set at 600 feet with 100 sacks cement,

100# Flocele, 5 sacks CC, cement circulated.

Filled hole full of heavy mud from 4596 feet to 600 feet.

Dumped 25 sacks cement filling hole from 600 feet to 540 feet.

Mud from 540 feet to 28 feet. Dumped 10 sacks of cement

from 28 feet to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 21 1953

CONSERVATION DIVISION  
Wichita, Kansas

*Handwritten signature*  
District Conservation Agent

Date August 24, 1953

PLUGGING  
FILE SEC 21 124 5W  
BOOK PAGE 24 LINE 28