

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
OCT 26 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Patterson Well No. # 1

Location NE NE Sec. 33 Twp. 33 Rge. 9 (E) (W) W

County Harper Total Depth 4959'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 2:00PM Day 23rd Month Oct. Year 1966

The Above well was plugged as follows:

246' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged with
1 sack of Gel-Mud and 1/2 sack of hulls on fluid at 240', and cemented with
25 sacks, through the drill pipe. Hole was filled with drilling mud to
50', bridged with 1/2 sack of Gel-Mud and 1/2 sack of hulls on fluid at 50',
and cemented with 20 sacks to the base of the cellar. Rat and mouse holes
bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aubie Elving
Well Plugging Supervisor

DATE 10/26/66
INV. NO. 4179-W