

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Wood Oil Company

Complete Address: 800 Midstates Bldg., Tulsa, Oklahoma

Lease Name Whaley Well No. # 1

Location C NW NW Sec. 25 Twp. 33 Rge. 9 (E) (W) W

County Harper Total Depth 4605

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Rex and Morris Drilling Company

Address: Box 334, El Dorado, Kansas License No.

Operation Completed: Hour 10:00PM Day 2nd Month September Year 1964

The Above well was plugged as follows:

251' of 8 5/8" surface pipe, cement circulated with 140 sacks. Hole was
filled with drilling mud to 250', 1st cementing plug, bridged solid
with hulls, on fluid at 250', and cemented with 25 sacks. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged solid with
hulls, on fluid at 40', and cemented with 10 sacks to the base of the
cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/4/64

INV. NO. 9463-W