

15135-20311-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

3100'

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Braden Drilling, Inc.

Complete Address 1620 Vickers KSB&T Bldg., Wichita, Kansas 67202

Lease Name Mellick "A" Well No. 1

Location C NE SW Sec. 35 Twp. 18 Rge. (E) (W) 21

County Ness Total Depth 4230'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 12:30 P Day 20 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 4230' 8 5/8 csg set at 250' cwc: 160 sk.

5 1/2 csg set at 4226' cw 200 sk cmt.

Filled 5 1/2 csg W/sd (4200-4230) Dumped 5 sk cmt. W/dump bailer. (4165-4200)

Cutoff and recovered 3100' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls, release plug and pumped 120 sk 50-50 poz W/4% added gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Muesel
Well Plugging Supervisor

DATE 1-7-72

INV. NO. 4864-W