

15:135-20097-0001

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Braden Drilling, Inc.

Complete Address 1620 Vickers KSB&T Bldg., Wichita, Kansas 67202

Lease Name Ryersee (SWD) Well No. 1

Location C SW SE Sec. 35 Twp. 18 Rge. (E) (W) 21

County Ness Total Depth 4192'

Abandoned Oil Well Gas Well Input Well SWD Well XXX D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering

Address Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 3:30 P Day 20 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 4192' 8 5/8 csg set at 293' cwc

5 1/2 csg set at 4188' cw 125 sk cmt. Two stage collar at 1420' cwc to surface.

5 1/2 csg PBTB 3860' and perf. (3512-3520)

No pipe recovered

Pumped down 5 1/2 csg with 40 sk 50-50 poz cmt W/6% total gel, 35 sk gel & water

W/500 lbs hulls, -released plug and pumped 50 sk 50-50 poz cmt W/6% total gel.

Max. pres. 750 lbs. SI pres. 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Wassen
Well Plugging Supervisor

DATE 1-7-72
INV. NO. 4865-W