

15:135:00566-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 9 - 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Stickle Drilg Co  
Complete Address: 1100 Betting Bldg. Wichita Kansas  
Lease Name Pyersall Well No. 1  
Location C- NW- SE Sec. 35 Twp. 18 Rge. 21 (E) (W) -  
County Ness Total Depth 4247  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:       
Plugging Contractor: Knights Casing Pulling  
Address: Chase Haus License No. 436  
Operation Completed: Hour 5PM Day 31 Month July Year 1965

The Above well was plugged as follows:

Total Depth - 4247 - 8 7/8 at 209' - 5 1/2 - 4226 - (on 100 ft. Pipe 4100/4124)  
Well had been capped as it was flowing - Removed cap  
Shot 5 1/2 at 2500' and pulled same to 2200' - Attached  
Pumper to 5 1/2 and pumped 20 sac of weight mud and  
10 sac gel mud to stop well from flowing. Pulled 5 1/2 out  
of hole - attached pumper equipment and squeezed hole with  
125 sac cement. One 8-2-65 - removed plug container and cement  
was within two ft of top of 8 7/8 surface pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arthur P. Luke  
Well Plugging Supervisor

DATE 8/9/65  
INV. NO. 1599-W