

*9*

KANSAS  
STATE CORPORATION COMMISSION

15-127-19038-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 2 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Rosen & Schreiner

Complete Address: 701 Union Center Bldg, Wichita, Kansas

Lease Name Grass Well No. 7

Location NW NE SE Sec. 35 Twp. 16 Rge. 5 (E) (W)

County Morris Total Depth 2212'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 305, Chase, Kansas License No. 436

Operation Completed: Hour 2:30PM Day 30 Month 4 Year 63

The Above well was plugged as follows:

Filled hole w/ sand from T.D. 2212' back to 2190' ran 5 sax cement w/ dump bailer.

Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 2155' back to 145' set a

10' rock bridge and ran 20 sax cement from 135' back to 75'. Filled hole w/ mud from

75' back to 30' set a 5' rock bridge and ran 8 sax cement from 25' back to zero 3'

below ground level. 8 5/8" surface pipe 3' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOTCED

Signed: *William J. Jones*  
Well Plugging/Supervisor

DATE 5-2-63

INV. NO. 7465-E