

R.

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 13 1977

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-115-20124-0000 CONSERVATION DIVISION  
Wichita, Kansas (of this well)

Operator's Full Name Frank J. Black

Complete Address Box 250 McPherson, Kansas 67460

Lease Name Deines Well No. # 3

Location NW SE NE Sec. 29 Twp. 17 Rge. 4 (E) 1/W

County Marion Total Depth 2453'

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Voth Casing Pulling

Address Arkansas City, Kansas License No. # 684

Operation Completed: Hour 1 PM Day 11 Month 6 Year 77

The above well was plugged as follows:

8 5/8"-151'-Circulated w/cement. 5 1/2"-2400'-Cemented. Sand to 2375'. 5 Sax.  
Cement. Mud to 175'. Bridge 175' to 165', 25 Sax. Cement. Mud to 40'.  
Bridge 40' to 30'; 10 Sax. Cement 30' to 0. Pulled 2100'-5 1/2"-Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 6-13-77

INV. NO. 4112-F