

15-007-10009-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1964
1-23-64

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Stewart Well No. # D-1

Location NE SE SE Sec. 15 Twp. 32 Rge. 11 (E) (W) W

County Barber Total Depth 3597

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 342, El Dorado, Kansas License No. 547

Operation Completed: Hour 2:30PM Day 20th Month Jan. Year 1964

The Above well was plugged as follows:

191' of 8 5/8" surface pipe, cement circulated. 3589' of 5 1/2" long string,
cemented with 75 sacks. Bottom of hole was sanded to 3580', and cemented
with 5 sacks. Hole was gassy and was killed with water. Due to this gas
condition a squeeze job was necessary. 15 sacks of Gel Mud and 80 sacks
of cement was pumped into the surface pipe, through a swage, to a pressure
of 200 lbs.

The cementing was done by Halliburton Cementing Co.

3000' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/22/64

INV. NO. 8496-W

Signed: Archie Elving
Well Plugging Supervisor