

15-007-01945-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1965
8-12-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pan American Petroleum Corporation

Complete Address: P. O. Box 432, Liberal, Kansas

Lease Name V. G. Coleman Well No. # 1

Location NE SW NE Sec. 36 Twp. 32 Rge. 11 (E) (W) W

County Barber Total Depth 4567'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:45PM Day 9th Month August Year 1965

The Above well was plugged as follows:

266' of 8 5/8" surface pipe, cement circulated. 4506' of 5 1/2" long
string, cemented with 250 sacks. No recovery of any pipe. Hole had
developed in the 5 1/2" long string, and cement had been pumped in to
circulated, through 8 5/8" surface pipe. 5 1/2" long string was filled
Gel-Mud to 250', rock bridge from 250' to 240', and cemented with 6
sacks, bringing the top of the cement to 192'. Hole was filled with
Gel-Mud to 40', rock bridge from 40' to 30', and cemented with 4 sacks
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-12-65

INV. NO. 1614-W

Signed: Achie Elving
Well Plugging Supervisor