

15-077-30191-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1966

7-22-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Wright Well No. # 1

Location C NE SW Sec. 28 Twp. 32 Rge. 9 (E) (W) W

County Harper Total Depth 4778'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No.

Operation Completed: Hour 6:00PM Day 21st Month July Year 1966

The Above well was plugged as follows:

249' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole was
filled with drilling mud to 240', 1st cementing plug, bridged with 1 sack
of Gel-Mud and 1/2 sack of hulls on fluid at 240', and cemented with 30
sacks, through the drill pipe. Hole was filled with drilling mud to 50',
2nd cementing plug, bridged with 1/2 sack of Gel-Mud and 1/2 sack of hulls on
fluid at 50', and cemented with 25 sacks to the base of the cellar.
Rat and mouse hole bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 7/22/66
INV. NO. 3614-10