

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
Rev. 1-1-68  
**RECEIVED**  
STATE CORPORATION COMMISSION

MAR 02 1977

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 135 - 21266 - 0000 (of this well)

Operator's Full Name Meltzer Oil Company

Complete Address Drawer "B", Great Bend, Kansas 67530

Lease Name Schwieb "B" Well No. 1

Location C SE NE Sec. 13 Twp. 19 Rge. (E) (W) 22

County Ness Total Depth 4360'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 4:30 P Day 1 Month 3 Year 1977

The above well was plugged as follows:

Total Depth 4360' 8 5/8 csg set 410' cwc 390 sx.

4 1/2 csg set 4360' cw 175 sx. Top perf. (4288')

Filled 4 1/2 csg W/sd (4360'-4275') dumped 3 sk cmt W/dump bailer. (4275'-4245')

Cutoff & recovered 3332' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 18 sk gel & water W/100 lbs

hulls, released 8 5/8 plug & followed with 85 sx 50-50 poz 2% -displaced with

7 sk gel & water -& capped with 15 sx 50-50 poz 2% & shutin. PP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leo Messing  
Well Plugging Supervisor

DATE 3-2-77

INV. NO. 4722-W