

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-125 22 075.0000

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name EDWARD P. LEIMER

Complete Address BOX 17 MAJOR ROUTE - HAYS, MO. 67601

Lease Name SCHWEIN Well No. SE1

Location SE-SE-NE Sec. 12 Twp. 19 Rge. 22 (East) (West)

County NESS Total Depth 4297 FE

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor MELO CASING PULLING

Address BOX 176 CHASE, MO. 67524 License No. 683

Operation Completed: Hour: 11:25 AM Day: 27 Month: AUG. Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

8 5/8" - 440 FE SD. CUL. w/out. -> 5 1/2" SET AT 4296 FE w/75 ST CMT.  
PLUG. BACK T.D. 4288 FE -> PERF'S TOP. 4272 - 86'  
SAND BOTTOM TO 4200 FE w/5 ST CMT. -> SHOT 6 TIMES - RECOVERED 3020 FE  
ORDERED 150 ST 5% POZ MIX 4% GEL - 3% CA-CL. - 25 ST GEL -> 6 ST HULLS + 8 5/8" PLUG.  
PUMPED IN 8 5/8" SD. WITH PUMP TRUCK.  
PUT IN - 4 ST HULLS, 15 ST GEL -> 1 ST HULLS -> 70 ST CMT.  
9 ST GEL -> RELEASED PLUG. AND 80 ST CMT.  
MAX. PRESSURE 1200 LBS

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, KS  
8 1981 28-81  
CEMENTED BY ALLIED  
Signed: Marvin Schmidt  
Conservation Division Agent

DATE 9-25-81  
INV. NO. 7443W