

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -135 -21,279-0000 (of this well)

RECEIVED
SEP 26 1977
9-20-77
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Twin Western Resources, Inc.
Complete Address 920 Union Center, Wichita, Ks.
Lease Name ~~MARGHEIM~~ Margheim Well No. 1
Location C. NE SW Sec. 11 Twp. 19 Rge. (E) (W) 22
County Ness Total Depth 4347'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor H-30 Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 3 P Day 24 Month 9 Year 1977

The above well was plugged as follows:

RTD 4347' 8 5/8 csg set 295' cwc 200 sk. Plg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 9-29-77
INV. NO. 5907-W