

KANSAS

RECEIVED CP-3  
STATE CORPORATION COMMISSION 68

STATE CORPORATION COMMISSION

OCT 30 1978

CONSERVATION DIVISION AGENT'S REPORT CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 135 - 20,445-0000 (of this well)

Operator's Full Name Mull Drilling Co., Inc.

Complete Address 221 N. Main, Suite 300, Wichita, Kansas 67202

Lease Name Rein Well No. 1

Location C SE SE Sec. 12 Twp. 19 Rge. (E) (W) 22

County Ness Total Depth 4273'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Sargent Casing Pulling

Address Liberal, Kansas License No. 511

Operation Completed: Hour 12 N Day 27 Month 10 Year 1978

The above well was plugged as follows:

Total Depth 4273' 8 5/8 csg set 356' cwc200 sk.

5 1/2 csg set 4269' cw 125 sk cem.

Pumped 30 sk cem plug down 5 1/2 csg. top of cem. 3625'.

Cutoff & recovered 1826' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 15 sk gel & water W/100 lbs hulls -followed

with 80 sk cem. -displaced with 5 sk gel & water & capped with 20 sk cem. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 10-31-78  
INV NO. 8423-W

Signed: Reo Massey  
Well Plugging Supervisor