

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company, Inc.

Complete Address 1625 Wichita Plaza Wichita, Kansas 67202

Lease Name Reim Well No. 2

Location NE SE Sec. 12 Twp. 19 Rge. (E) (W) 22

County Ness Total Depth 4320'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 5 A Day 16 Month 9 Year 1971

The above well was plugged as follows:

RTD 4320' 8 5/8 csg set at 355' cwc Cmt. Mat. 50-50 pez 2% gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 9-22-71

INV. NO. 4372-W