

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County, Sec. 1 Twp. 20S Rge. 22 (E) W. (W)

Location as "NE/CNW/SW" or footage from lines 660' FNL, 510' FEL

Lease Owner Cities Service Oil Company

Lease Name Foos "A" Well No. 3

Office Address Box 308, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 4 19 65

Application for plugging filed May 4 19 65

Application for plugging approved May 4 19 65


Plugging commenced May 5 19 65

Plugging completed May 5 19 65

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production - 19 -

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4430 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	516'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4430-510', heavy mud.
510-445', 20 sacks cement.
445-240', mud.
240-175', 20 sacks cement.
175-40', mud.
40'-base of cellar, 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1965
5-12-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.

Address Box 359, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
W. J. Devaney (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Box 308, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May, 19 65

[Signature]

My commission expires December 6, 1966

Notary Public.

WELL RECORD

15735-30044000

WILDCAT _____

DISCOVERY _____

POOL _____

Company Cities Service Oil Company Well No. 3 Farm Foos "A"

Location 660' from N.L. & 510' from E.L. Sec. 1 T. 20S R. 22W

Elev. Ser. K.B. 2258' D.F. 2255' Gr. 2251' Co. Ness State Kansas

N. I. P. P. & A. 5/5/65 A. I. P. _____ Grav. _____

Pay Zones _____

Perforations None

Acid None Hydrafrac _____

T. D. 4430' P. B. T. D. _____ N. T. D. _____ Drlg. Comm. 4/23/65 Drlg. Comp. 5/4/65

CASING RECORD:

8 5/8" @ 516' w/275 sacks.

Contractor Peel Brothers, Inc.

Log Tops:

Formation Record:

Formation	Depth:
shale	0 - 518
shale & sand	930
sand	1140
shale & red bed	1480
red bed & shale	1499
anhydrite	1532
shale & shells	2240
lime & shale	2920
shale & lime	3290
lime & shale	3755
lime	3762
shale	3766
lime	4380
lime & chert	4392
lime, shale & chert	4409
lime & chert	4430 R.T.D.

Heebner	3762 (-1504)
Toronto	3780 (-1521)
Lansing	3809 (-1551)
Base Kansas City	4136 (-1878)
Pawnee	4227 (-1970)
Fort Scott	4311 (-2053)
Cherokee	4334 (-2076)
Conglomerate	4370 (-2112)
Cherty Conglomerate	4376 (-2118)
Warsaw	4396 (-2138)
Osage	4400 (-2142)
Log Total Depth	4430
Pen. Miss. 34'	

Eastman

1/2° -	1550
1/2° -	2260
3/4° -	2813
1/2° -	3290
1/2° -	3915
1/2° -	4260

VJQ/ng
8/5/65

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1965

CONSERVATION DIVISION
Wichita, Kansas