

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-22,865-0000

LEASE NAME Dechant

WELL NUMBER 2

SPOT LOCATION NWSWSE

SEC. 1 TWP. 20 RGE. 22 (E) or (W)

COUNTY Ness

Date Well Completed 7-24-85

Plugging Commenced 8:00 P.M.

Plugging Completed 11:00 P.M.

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Dreiling Ltd. of Colorado

ADDRESS 410 - 17th St., Suite 1140, Denver, Co. 80202

PHONE # (303) 623-6144 OPERATORS LICENSE NO. 5804

Character of Well D&A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing formation None Depth to top _____ bottom T.D. 4393'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	30% H ₂ O, 70% mud	4374'	95'	8-5/8"	371'	None
	120' total					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Hole was full of heavy mud. Cement was pumped through drill pipe as follows: 1st cement plug at 1478' with 50 sacks, 2nd cement plug at 700' with 70 sacks, 3rd cement plug at 405' with 50 sacks, 4th cement plug from 40 feet to surface with 10 sacks, Rathole with 15 sacks, mousehole with 10 sacks--205 sacks total 60-40 Poz. 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287
 Address Ness City, Kansas

STATE OF Colorado COUNTY OF Denver, ss.

Leslie Olson (employee of operator) or
 (XXXXXXXX) of above-described well, being first duly sworn on oath, says: That
 I have knowledge of the facts, statements, and matters herein contained and
 the log of the above-described well as filed that the same are true and
 correct, so help me God.

(Signature) Leslie Olson
 (Address) 410 - 17th St., Suite 1140
 Denver, Colorado 80202

SUBSCRIBED AND SWORN TO before me this 31 day of July, 1985

Lorraine C. Murphy
 Notary Public

My Commission expires: 9-2-87
 STATE CORPORATION COMMISSION

Form CP-4 1-84
 Revised 06-83

ANG 2 1025
 8-2-85
 CONSERVATION DIVISION
 Wichita, Kansas