

15-135-22295-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ness SEC. 1 TWP. 20S RGE. 22 XE/W
Location as in quarters or footage from lines:
SE NE

Lease Owner Sutherland Building Materials, Inc.
Lease Name Foos Well No. 1
Office Address 212 N. Market, Suite 400, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry hole
Date Well Completed September 27, 1982
Application for plugging filed _____
Plugging commenced September 27, 1982
Plugging completed September 27, 1982
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes-oral

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 4420

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	501	8 5/8	493	none

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Hole plugged with 50/50 pozmix, 4% gel, 3% CaCl
as follows:

- 60 sacks at 900 feet
- 40 sacks at 560 feet
- 10 sacks & solid bridge plug at 50 feet
- 10 sacks in rathole
- 5 sacks in mousehole

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1982
10-20-82
CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc., Russell, Ks.

STATE OF Kansas COUNTY OF Sedgwick, ss. of contractor
John Jay Darrah, Jr., president (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) By [Signature]
Mallard Drilling Co., Inc.
405 Century Plaza, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of October 1982

[Signature]
Dianne R. Fowler, Notary Public.

My Commission expires: August 25, 1984

DRILLERS LOG

15.13S-222950000

COMPANY: Sutherland Building Material, Inc.
 CONTRACTOR: MALLARD DRILLING CO., INC.
 405 Century Plaza
 Wichita, Kansas 67202

WELL NAME: #1 Foos
 DESCRIPTION: SE NE 1-20S-22W
 Ness Co., Ks.

RIG NO.: 1 COUNTY: Ness
 TOTAL DEPTH: 4420 ELEVATION: 2234 gr.
 COMMENCED: September 20, 1982 COMPLETED: September 27, 1982

CASING RECORD:
 12 jts. 8 5/8" 23# new surface

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, sand	0	1486	Ran 493' new 23# 8 5/8" surface casing, set and cemented with 325 sacks 60/40 pozmix, 3% CaCl, 2% gel at 501'. Cement circulated. Plug down @ 12:00 a.m., September 21, 1982.
Anhydrite	1486	1517	
Shale w/sand	1517	3022	
Shale	3022	4088	
Lime	4088	4420 TD	
			Ran 1 drill stem test
			Ran 1 electric log
			Hole plugged with 50/50 pozmix, 4% gel, 3% CaCl as follows: 60 sacks at 900'; 40 sacks at 560'; 10 sacks & solid bridge at 40'; 10 sacks in rathole, 5 sacks in mousehole. Plugging completed at 5:30 p.m., September 27, 1982.

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify that this is a true and correct copy of the log of the #1 Foos well, to the best of my knowledge.

John Jay Darrah, Jr.
 John Jay Darrah, Jr., President

SUBSCRIBED AND SWORN to before me this 15 day of October, 1982.

Dianne R. Fowler
 Dianne R. Fowler, Notary Public

My Commission Expires:
 August 25, 1984

RECEIVED
 STATE CORPORATIONS COMMISSION

OCT 20 1982

CONSERVATION DIVISION
 Wichita, Kansas