

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


1535 21383 0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 1 Twp. 20 Rge. 22 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SE SW

Lease Owner Vincent Oil Corporation
Lease Name Schneider No.2 Well No. 2
Office Address 901 Union Center Building, Wichita 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 10/24/77 19
Application for plugging filed 10/24/77 19
Application for plugging approved 10/24/77 19
Plugging commenced 10/24/77 19
Plugging completed 10/24/77 19
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4405
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	483'	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug at 600' with 50 sacks 50/50 Poz 2% gel
Middle Plug at 300' with 25 sacks 50/50 poz, 2% gel
Top and bridge at 40' with 10 sacks 50/50 Poz 2% gel
2 sacks in rathole
Job complete at 8:30 p.m. 10/24/77

RECEIVED
CONSERVATION COMMISSION
NOV 01 1977
11-1-77
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
James C. Remsberg (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
James C. Remsberg
200 Douglas Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29 day of October, 19 77

Mary Lou Taylor
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

15-135-21383-0000

OPERATOR: Vincent Oil Corporation
 901 Union Center Building
 Wichita, Kansas 67202

LEASE: Schneider No. 2
 C SE SW Sec. 1-20S-22W
 Ness County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 10/17/77

COMPLETED: 10/24/77

RTD: 4405'

CASING: 8-5/8" set at 483' with 300 sacks cement

0' to 488' Shale & Shells (12 1/4" Surface Hole)
 488' to 690' Shale
 690' to 925' Shale & Shells
 925' to 1138' Sand
 1138' to 1489 Shale & Shells
 1489' to 1522' Anhydrite
 1522' to 2335' Shale & Shells
 2336' to 2875' Lime & Shale
 2875' to 3170' Lime
 3170' to 4235' Lime & Shale
 4235' to 4405' Lime
 4405' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 01 1977
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
 hereby state that the above and foregoing is a true and accurate copy
 of the Schneider No. 2 well for Vincent Oil Corporation.

James C. Remsberg
 James C. Remsberg

Subscribed and sworn to me this 29th day of October, 1977

Mary Lou Taylor
 Mary Lou Taylor, Notary

My commission expires January 17, 1981

