


15-007-3030-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 1 Twp. 31 Rge. (E) 14 (W)

Location as "NE/CNW%SW%" or footage from lines SW NE NE
Lease Owner Aylward Drilling Company
Lease Name Skinner "F" Well No. 2
Office Address 909 First National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 28 19 65
Application for plugging filed May 28 19 65
Application for plugging approved May 28 19 65
Plugging commenced May 28 19 65
Plugging completed May 28 19 65
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving
Producing formation Depth to top Bottom Total Depth of Well 4539 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	175'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole with 37 sacks cement
Mud to 190' set plug and 25 sacks cement
Mud to 40' set plug and 15 sacks cement
Bridged rathole and 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1965
6-15-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company tools
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Duane Jessup (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Duane Jessup
909 First National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of June, 1965

Joseph A. Hess
JOSEPH A. HESS Notary Public.

My commission expires May 14, 1968



15-057-30130-0000

SKINNER "F" #2

Casing Record: Company: Aylward Drilling Company Location: SW NE NE
 8 5/8" - 175' Contractor: Aylward Drilling Company Sec. 1-31-14W
 Barber County
 Kansas
 Commenced: May 16, 1965
 Completed: May 28, 1965 Elev. 1824 K.B.

	From	To	Remarks
Soil & Red Rock	0	25	Set 8 5/8" surface pipe @ 175'
Gyp	25	55	w/175 sacks cement.
Red Bed	55	95	
Red Bed w/Gyp streaks	95	110	Geological Tops:
Red Bed	110	1007	
Shale	1007	1695	Heebner 3761
Shale & Lime	1695	1865	Douglas Shale 3791
Lime	1865	2330	Douglas Sandstone 3894
Shale	2330	2455	Brown Lime 3934
Shale w/Broken Lime	2455	2485	Lansing-Kansas City 3946
Lime & Shale	2485	2795	Base/Kansas City 4368
Shale	2795	3037	Marmaton 4377
Lime & Shale Streaks	3037	3065	Mississippian 4444
Shale & Lime	3065	3805	Kinderhook Shale 4474
Shale	3805	3893	Maquoketa 4522
Sand	3893	3930	Viola 4534
Lime	3930	4105	
Lime & Shale	4105	4160	DST 4445-60 Open 45"
Lime	4160	4475	Rec. 100' gas in pipe & 20' mud
Shale	4475	4500	IBHP 15#/20" - FBHP 38#/20"
Shale & Lime	4500	4528	FP 15-15#.
Lime	4528	4539 T.D.	
			DST 4523-28 Open 30"
			Rec. 4' mud
			IBHP 0#/20" - FBHP 0#/20"
			FP 0-0#
			DST 4527-39 GTS/5" TSTM Open 60"
			Rec. 20' O&GCM & 360' Muddy SW
			IBHP 536#/30" - FBHP 521#/30"
			FP 61#-183#.

4534
1824
2710

D & A

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1965
6-15-65
CONSERVATION DIVISION
WICHITA, KANSAS

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Subscribed and sworn to before me this 3rd day of June, 1965

Duane Jessup

Joseph A. Hess
Notary Public

My commission expires May 14, 1968