

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21,517-0000

LEASE NAME Lonker

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

100' Ft. from S Section Line  
E/NE S $\frac{1}{2}$  SW  
Ft. from E Section Line

SEC. 28 TWP. 32 SRGE. 11 (W)

COUNTY Barber

LEASE OPERATOR Hummon Corp.

ADDRESS 400 One Main Place, Wichita, KS 67202

PHONE# (316) 263-8521 OPERATORS LICENSE NO. 5050

Date Well Completed 3/17/83

Character of Well Oil

Plugging Commenced 5/31/85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/14/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3714

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	204	None
				4 1/2	3713	2855

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plug back at 3670; Sand from 3670 to 3570, 4sx cement with dump bailer from 3570 to 3540  
Sun Cementing pump in 3sx hulls, 10sx jell, 50sx cement, 8sx jell, 1sx hulls, 100sx cement  
60-40 POZ; 6% jell

Metz and E. Morgenstern on location

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp.

License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

STATE CORPORATION COMMISSION

STATE OF Kansas

COUNTY OF Barber

, ss. 6-19-85

JUN 19 1985

Elmo Morgenstern

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CAREN J. McCULLOUGH  
NOTARY PUBLIC

(Signature) Elmo Morgenstern

STATE OF KANSAS

(Address) \_\_\_\_\_

My Appt. Exp. 6-29-87

SUBSCRIBED AND SWORN TO before me this 14 day of June, 19 85

Caren J. McCullough  
Notary Public

My Commission Expires: June 29, 1987

15-007-21517-0000

DRILLERS LOG

#1 Lenkner

CASING RECORD:	COMPANY:	Hummon Corporation	DESCRIPTION:
8 5/8" @ 204'	CONTRACTOR:	Big-H Drilling, Inc.	100' E/ N $\frac{1}{2}$ S $\frac{1}{2}$ SW $\frac{1}{4}$
w/ 145 sx. cement	COMMENCED:	October 31, 1982	Section 28-32S-11W
4 1/2" @ 3713'	COMPLETED:	November 6, 1982	Barber County, Kansas
w/ 125 sx cement			ELEVATION: 1502 KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Beds	0	210	
Red Beds & Shale	210	1043	
Shale & Lime	1043	1612	
Lime & Shale	1612	1908	
Shale & Lime	1908	2344	
Lime & Shale	2344	3207	
Shale & Lime	3207	3419	
Lime & Shale	3419	3714	
RTD		3714	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

BIG-H DRILLING, INC.

*Karen R. Tennis*  
 \_\_\_\_\_  
 Karen R. Tennis

Subscribed and sworn to before me this 12th day of November, 1982.

SAMUEL MENDOZA  
 SEDGWICK COUNTY, KANSAS  
 MY APPT. EXP. 2/13/86

*Samuel Mendoza*  
 \_\_\_\_\_  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 24 1985  
 5-24-85  
 CONSERVATION DIVISION  
 Wichita Kansas