


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 28 Twp. 32S Rge. 11E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

NE SW
Lease Owner Pickrell Drilling Company
Lease Name Lyman A Well No. 1
Office Address 110 N. Market, Suite 205, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Oil
Date Well completed 9-16- 1978
Application for plugging filed 6-4- 1979
Application for plugging approved 6-5- 1979
Plugging commenced 6-23- 1979
Plugging completed 6-27- 1979
Reason for abandonment of well or producing formation _____

Depleted
If a producing well is abandoned, date of last production
4-20- 1979

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation Douglas Depth to top 3645 Bottom 3701 Total Depth of Well 4827
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Douglas	Oil & Water	3653	3657	8 5/8"	274	None
				4 1/2"	3779	2883

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Sand from 3636 to 3575
- 4 Sacks cement from 3575 to 3545
- Ripped 2883
- Built wooden bridge at 275
- Rock from 275 to 274
- 4 1/2 yards of ready mix to the top.

RECEIVED
STATE CORPORATION COMMISSION

OCT - 2 1979
10-2-79

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation.

STATE OF Kansas COUNTY OF Barber, ss.
Elna R. Morgenstern (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elna R. Morgenstern
Medicine Lodge, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 1979.

Jessie Hamilton
Notary Public.

My commission expires April 4, 1982.

PAID

ROTARY DRILLING LOG

15-007-20651-0000

COMPANY: PICKRELL DRILLING COMPANY
205 LITWIN BLDG.
WICHITA, KS. 67202

Rotary Drilling Commenced 8-11-78

LOCATION: LYMAN A #1
App NE SW Sec. 28-32S-11W
Barber County, Kansas

Rotary Drilling Completed 10-16-78

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: Surf. casing 8 5/8" set at 274' with 180 sx.
Prod. casing 4 1/2" set at 3779' with 150sx.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Topsoil	40
Shale & Red Bed	275
Red Bed	415
Shale	1325
Shale w/Lime Strks.	1715
Shale & Lime	1942
Lime & Shale	2153
Lime & Shale	2362
Lime & Shale	2537
Lime & Shale	2767
Lime & Shale	2970
Lime & Shale	3140
Lime & Shale	3294
Lime & Shale	3442
Lime & Shale	3590
Lime & Shale	3690
Lime	3720
Lime & Shale	3739
Shale & Lime Sand	3862
Shale & Lime	3975
Lime & Shale	4089
Lime & Shale	4195
Lime & Shale	4295
Lime & Shale	4382
Lime & Shale	4470
Lime & Shale	4575
Shale & Lime	4660
Lime & Shale	4700
Lime	4766
Lime	4821
Lime	4827

RECEIVED
STATE CORPORATION COMMISSION

JUN - 6 1979
6-6-79
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By *[Signature]*
Attorney-in-Fact

C. W. Sebitts

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 25 day of January, 19 79, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: _____

[Signature]
Notary Public

Jo Ann Sarver

