

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21457-00-0
12-9-82

LEASE NAME Lukens

WELL NUMBER 3

2920 Ft. from S Section

2310 Ft. from E Section

SEC. 28 TWP. 23 RGE. 11 (E) (W)

COUNTY Barber

Date Well Completed 12-9-82

Plugging Commenced 4-16-93

Plugging Completed 1:45 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Farrar Pump & Supply Co., Inc.

ADDRESS P.O. Box 209

PHONE# (316) 886-3763 OPERATORS LICENSE NO. 3399

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-16-93

by Steve Pfiefer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Douglas Depth to Top 3650 Bottom 3716 T.D. 3800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	200	0
				5 1/2	3800	2581

Describe in detail the manner in which the well was plugged, indicating where the mud filter placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from ___ feet to ___ feet each

Bottom plug: Sanded to 3600 & bailed 5 sx cement.

Top plug: Pumped 300 lb hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lb hulls, wiper plug 100 sx cement 60/40 with 6% gel. Had maximum pressure of 500 lbs, and shut in pressure of 300 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 C

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Farrar Pump & Supply Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke

(Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the statements, and matters herein contained and the log of the above-described well as all the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas

RECEIVED

SUBSCRIBED AND SWORN TO before me this 20 day of APRIL 1993



Anna K. Burke
Notary Public

My Commission Expires: 4-30-96

APR 21 1993
4-21-93
CONSERVATION DIVISION
Wichita, Kansas
Revised