

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21,802-

LEASE NAME Thomas "A" #1

WELL NUMBER "A" #1

SPOT LOCATION NE SE SE

SEC. 27 TWP. 32 RGE. 11 (E) of (W)

COUNTY Barber

Date Well Completed \_\_\_\_\_

Plugging Commenced 8-4-84

Plugging Completed 8-10-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Mineral Management Corp.

ADDRESS 2927 Keywest Court, Wichita, Ks. 67204

PHONE # (838-1383-264-0661) OPERATORS LICENSE NO. 5264

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 2880'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	260'	None
				4-1/2"	2870'	2,324.22'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 2770' and 4 sacks cement Shot casing at 2400' and 2250'. Pulled 57 joints of 4-1/2" casing. Squeezed well with 3 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 100 sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111  
Address Box 698, Great Bend, Ks. 67530

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 13th day of August, 1984

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 7-26-87

Iona M. Leatherman  
Notary Public

My Commission expires: