

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-007-21381-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Woolsey Petroleum Corporation KCC LICENSE # 5506 6/99
(owner/company name) (operator's)

ADDRESS 1966 SE Rodeo Drive Rd. Box 168 CITY Medicine Lodge

STATE Kansas ZIP CODE 67104 CONTACT PHONE # (316) 886-5606

LEASE Palmer C WELL# C-1 SEC. 30 T. 325 R. 12 (~~East~~/West)

- - - NW - NE SPOT LOCATION/QQQQ COUNTY Barber

660 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM (E) W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A ~~XX~~ SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 320' CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 4615' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs @ 4529-31', 4553-60', CIBP @ 4450', Perf @ 4298'-4304' - CIBP @ 4250' perf 4056'-60', 3962'-72'
ELEVATION 1834'/1843' T.D. 4615' PBDT 4250' ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING CIBP @ 3930' + 2 sax cmt dn 8-5/8" csg. Pump 300# cotton seed hulls, 10 sax gel, 50 sax cement, 10 sax gel, 100##hulls, 8-5/8" wiper plug and 100 sax cmt Top off to surface in 24 hrs.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W. Durr PHONE# (316) 886-5606

ADDRESS 1966 SE Rodeo Drive Rd. Box 168 City/State Medicine Lodge, Ks. 67104

PLUGGING CONTRACTOR Clarke Corporation KCC LICENSE # 5105 6/99
(company name) (contractor's)

ADDRESS Medicine Lodge, Ks. 67104 PHONE # (316) 886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/14/99 AUTHORIZED OPERATOR/AGENT: Carl W. Durr
(signature)

RECEIVED
STATE CORPORATION COMMISSION

JAN 19 1999



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 19, 1999

Woolsey Petroleum Corporation
1966 SE Rodeo Dr. Rd., Box 168
Medicine Lodge, Ks. 67104

Palmer "C" #1
API 15-00721381
30-32S-13W
Sec. Barber
County

Dear Carl W. Durr,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888