

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 135-24046 0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR OBRIEN ENERGY RESOURCES CORPORATION KCC LICENSE # 32211
(owner/company name) (operator's)

ADDRESS 75 Congress Street CITY Portsmouth

STATE New Hampshire ZIP CODE 03801 CONTACT PHONE # (800) 291-1969

LEASE Schaben WELL# 1 SEC. 26 T. 19s R. 22w (~~XXXX~~ West)

- NE - NE - SW SPOT LOCATION/QQQQ COUNTY Ness

2310 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

2310 FEET (in exact footage) FROM E/(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 307.42 CEMENTED WITH 185 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2257/2265 T.D. 4450 PBDT _____ ANHYDRITE DEPTH (1502-1536)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING (1st Plug @ 1540' w/50sks)(2nd Plug @ 700' w/80sks)(3rd Plug @ 330' w/40sks)(4th Plug @ 40' w/10sks)(10sks In Mouse Hole)(15sks In Rat Hole)

205sks 60/40Poz 6%Gel w/1/4#FS/sk By Halliburton Completed @ 4:15PM 3/12/98
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Thomas H. Alm PHONE# (785) 625-5183

ADDRESS 1922 Whittier City/State Hays, Kansas 67601

PLUGGING CONTRACTOR Discovery Drilling, Inc. KCC LICENSE # 31548

ADDRESS P.O. Box 763 Hays, Kansas 67601 (company name) (contractor's)
PHONE # (785) 623-2920

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 3/12/98 @ 4:15PM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/20/98 AUTHORIZED OPERATOR/AGENT: _____
(signature)

MAR 31 1998
3-31-98
Wichita, Kansas