

15-007-30376-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 1 Twp. 37 Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines Center SE/4 NW/4

Lease Owner Time Petroleum Company

Lease Name Landwehr

Well No. 1

Office Address

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 9, 1957

Application for plugging filed May 9, 1957

Application for plugging approved May 9, 1957


Plugging commenced May 9 @ 3:00 P.M., 1957

Plugging completed May 9 @ 3:30 P.M., 1957

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4725 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

This well was plugged by Clyde Adams, filled with Rotary mud from 4725 to 250 feet.

Will plug with 20 sacks of cement, fill to 30 feet with Rotary mud, plug with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kirkpatrick Drilling Company

Address

STAMP: MAY 22 1958 CONSERVATION DIVISION WICHITA, KANSAS

STATE OF Kansas, COUNTY OF Barber, ss.

Clyde Adams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clyde Adams Clyde Adams

206 W. 7th Street, Winfield, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9 day of May, 1957

Notary Public: Majorie B. Bink

My commission expires December 19, 1960

PLUGGING FILE SEC 1 T 32 R 11 W BOOK PAGE 12 LINE 27

15-007-30376-0000  
**KIRKPATRICK DRILLING CO., INC.**  
**WICHITA, KANSAS**  
**DRILLERS WELL LOG**

#1 Landwehr  
 Center SE NW Section 1-32-11W  
 Barber County, Kansas

Commenced: 4-19-57  
 Completed: 5-9-57

From	To	Formation	Remarks
0	40	Surface Sand	
40	250	Red Bed - Shale	Ran 252' of 8 5/8" Surface pipe - cemented with 300 sacks of cement
250	335	Red Bed	
335	1265	Red Bed - Shale	
1265	1690	Shale, Shells	
1690	1990	Lime, Shale	
1990	2395	Lime	
2395	2865	Shale	
2865	3584	Shale, Lime	
3584	3671	Shale	Circulate for Samples @ 3670' for 55 minutes
3671	3710	Shale, Lime	
3710	3735	Sand	Circulate for Samples @ 3720'
3735	3780	Sand	DST #1 IBHP 30 minutes, open 1 hour, closed 30 minutes, recovered 185' salt water
3780	3840	Lime, KC	
3840	4256	Lime	
4256	4409	Lime, Shale	Circulate 1/2 hour @ 4401' for samples
4409	4415	Chert	Circulate for Samples 1 1/2 hours @ 4410', 1 hour @ 4415'. DST #2 4402-4415', recovered 60' of oil and gas cut mud
4415	4435	Lime	Circulate 1 hour @ 4435'
4435	4445	Lime, Chert	Circulate 1 hour @ 4445'
4445	4456	Lime	DST #3 @ 4445', open 45 minutes, closed 30 minutes, recovered 30' mud
4456	4510	Lime	Circulate 1 hour @ 4510' for samples
4510	4520	Lime, Chert	Circulate for samples 1/4 hour @ 4510', 3/4 hour at 4514'
4520	4540	Lime	
4540	4553	Shale	
4553	4597	Shale, Chert, Lime	
4597	4620	Shale	Circulate for samples 3/4 hour @ 4620'
4620	4650	Shale	
4650	4661	Lime	Circulate for samples 1/4 hour @ 4620' & 1 3/4 hours @ 4661'
4661	4661		DST #4, recovered 405' salt water
4661	4687	Lime, Chert	
4687	4710	Lime	
4710	4715	Sand	Circulate 1 hour @ 4715. DST #5, recovered 12' mud
4715	4725	Sand	Circulate for samples 1 hour @ 4720', 1 hr @ 4725'
4725	4725	Sand	DST #6, Recovered 10' rotary mud & 5' Salt water, ran Schlumberger
4725	TD	D & A	

**PLUGGING**  
 FILE NO. SEC 1 T 32 R 11 W  
 BOOK PAGE 12 LINE 27

I hereby certify the above and foregoing to be a true and correct copy of the log of Landwehr #1, located in the C SE NW of Section 1-32-11W, Barber County, Kansas to the best of my knowledge.

MAY 22 1957  
 KIRKPATRICK DRILLING CO., INC.  
 By R. C. Long  
 Secretary

Subscribed and sworn to before me this 11 day of May, 1957

My Commission Expires: Dec. 19, 1960  
Marjorie Brink  
 Notary Public