

15-877-20862-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD OPERATOR LICENSE NO.5447

Give All Information Completely
Make Required Affidavit

COUNTY Harper SEC. 25 TWP. 32S RGE. 9 W/W
Location as in quarters or footage from lines:
660' FNL - 1320' FWL

Locate Well
correctly on above
Section Platt.

Lease Owner Cities Service Company
Lease Name Prouse "A" Well No. 1
Office Address 209 East William, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry hole
Date Well Completed 12-11-82
Application for plugging filed 12-11-82 (verbal approval)
Plugging commenced 12-11-82
Plugging completed 12-11-82
Reason for abandonment of well or producing formation uneconomical for production

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation Stalnaker Depth to top _____ bottom T.D. 4010'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	314'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Spotted 100 sacks common cement plus 2% gel plus 2% CaCl₂ at 900'. Spotted 35 sacks
common cement plus 2% gel plus 2% CaCl₂ at 360'. Plug: 2 spotted 20 sacks common
cement plus 2% gel plus 2% CaCl₂ at 60' to base of cellar. Spotted 10 sacks common
cement plus 2% gel plus 2% CaCl₂ in rat hole. Plug and abandonment completed 12-11-82.

RECEIVED
STATE CORPORATION COMMISSION

IAN 17 1983
1-17-83
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Charles N. Richmond (employee of owner) or (~~owner~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

JACQUELINE PIERCE
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires:
2-27-85

(Signature) CR Richmond
C. N. Richmond
209 E. William (Address) Wichita, KS
67202

SUBSCRIBED AND SWORN TO before me this 13th day of January, 19 83

My Commission expires: February 27, 1985
Jacqueline Pierce Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS 67202

DRILLERS WELL LOG:

PROUSE "A" #1
SEC. 25-32S-9W
HARPER COUNTY, KANSAS

COMMENCED: 12-2-82

COMPLETED: 12-11-82

OPERATOR: CITIES SERVICE CO.

DEPTH FROM	TO	FORMATION	REMARKS
0	190	Shale-Shells	
190	590	Bedbed-Shale	Ran 7 jts. of #8 5/8"
590	1580	Shale-Shells	Csg. Set @ 314' Cemented
1580	3755	Lime-Shale	w/250 Sks.
3755	3865	Sand-Lime-Shale	PD @ 3:30 A.M. 12-3-82
3865	4010	Lime-Shale	

4010 - TD

State of Kansas }
County of Sedgwick }

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

[Signature]
James S. Sutton, II

Subscribed and sworn to before me
this 21st day of December, 1982.

[Signature]
Lola L. Costa - Notary Public

My Commission expires November 21, 1984.

RECEIVED
STATE CONSERVATION COMMISSION
DEC 25 1982
12-23-82
CONSERVATION DIVISION
Wichita Kansas

