

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-077-20,854-0000

LEASE NAME Brown

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER R-1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 26 TWP. 32S RGE. 9 (E) or (W)

COUNTY Harper

Date Well Completed 11-21-82

Plugging Commenced 5-2-88

Plugging Completed 5-5-88

LEASE OPERATOR TXO Production Corp.

ADDRESS 1660 Lincoln St. Suite 1800
Denver, CO 80264

PHONE# 303)861-4246 OPERATORS LICENSE NO. 5171

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on N/A (date)

by N/A (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? ---

Producing Formation Stalnaker Depth to Top 3714 Bottom 3726 T.D. 4076

E.L. 1465' G.L. (-2249) (-2261) (-2611)
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	263'	--
				4 1/2"	4075'	±2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged bottom w/15 sx Class 'A', 1-sx hulls, 10 sx poz mix, 4 1/2 rubber plug.
Cut & pulled ±2700' 4 1/2 csg. Plugged top of well w/ 5 sxs hulls, 10 sxs gel, plug, 100 sxs 65/35 poz-mix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address 107 W. Fowler, Box 187 Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TXO Production Corp.

STATE OF COLORADO COUNTY OF DENVER, ss.

Cory West (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Cory West

(Address) 1660 Lincoln St, Suite 1800

SUBSCRIBED AND SWORN TO before me this 9th day of Sept, 19 88

Maornip Glenn
 Notary Public

My Commission Expires: 11/25/88