

RECEIVED

NOV 26 2002

11-26-02  
KCC WICHITA

Well Plugging Record

K.A.R. -82-3-117

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-077-21,178-00-00  
LEASE NAME Brown C  
WELL NUMBER 1-26

TYPE OR PRINT

NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

660 Ft. from South Line of Section  
1320 Ft. from East Line of Section

LEASE OPERATOR McCoy Petroleum Corporation #5003 SPOT LOCATION C S2 SE  
ADDRESS P. O. Box 780208 Section 26 Township 32 Range 9 W  
CITY, STATE, ZIP Wichita, Kansas 67278-0208 County Harper  
PHONE # 316-636-2737 Date Well Completed 6/1/88  
Character of Well Gas Date Plugging Commenced 11/07/02  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 11/08/02

The plugging proposal was approved on 11/7/02 (date)  
by Doug Louis (KCC District Agent's Name)

Is ACO-1 Filed? yes If not, is well log attached?  
Producing Formation(s) Pennsylvanian Depth to Top Bottom T.D. 3991

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
				8-5/8"	250	0
				5-1/2"	3991	2802

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Sand at 3638', bailed 5 sacks cement. Shot pipe. 3038, 2802' worked free. Pulled to 1350'. Pump 35 sacks cement. Pull to 850', pumped 35 sacks cement. Pull to 300', circulated cement to surface with 55 sacks cement. Pulled rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc.  
Licence No. 31925  
Address 401 W. Main City: Lyons State: KS Zip 67554  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)

STATE OF KANSAS COUNTY OF Sedgwick, ss.

Scott Hampel (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.


(Signature) Scott Hampel  
(Scott Hampel, Engineering & Production Manager)

(Address) 453 S. Webb, Suite 310, P.O. Box 780208 City: Wichita State: KS Zip 67278

SUBSCRIBED AND SWORN TO me this 22 day of November, 20 02

Karen E. Houseberg  
(Notary Public)

My Commission Expires: 9/5/2006



Form CP-4 Revised 12-92

CP