

K-077-20940-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY HARPER SEC. 27 TWP. 32 RGE. 9 EW
Location as in quarters or footage from lines:
C-SE-NE 1980 ENL 660 EEL

Lease Owner Eagle Explorations, Inc
Lease Name SMITH Well No. 1-27
Office Address 107 N Market Wichita, Ks 67202
Character of Well (Completed as ~~Oil or Gas~~ Dry Hole): (C)(L)
Date Well Completed 9-26-1983
Application for plugging filed _____
Plugging commenced 9-26-1983
Plugging completed 9-26-1983
Reason for abandonment of well or producing formation NO

Locate Well
correctly on above
section plat.

PRODUCIBLE HYDROCARBONS

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well STAN MARCOTTE

Producing formation NONE Depth to top _____ bottom _____ T.D. 3907

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8" 24#	287'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. This well was plugged with a total of 115 sax
Class "A" Common cement, 2% Gel. as follows:

- 3907' to 900' Drilling Mud
- 900' to 806' 35 sax cement
- 806' to 310' Drilling Mud
- 310' to 216' 35 sax cement
- 216' to 60' Drilling Mud
- 60' to Surface 25 sax cement followed by Wood Plug
- 10 BBL. of fresh water was pumped ahead of each cement plug.
- 10 sax cement in Rat Hole
- 10 sax cement in Mouse hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

STATE OF Kansas COUNTY OF Sedgwick, ss.

Carl W. Durr (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Carl W. Durr


(Address) _____

ED AND SWORN TO before me this 28th day of September, 19 83

Sharon I. Olson

Sharon I. Olson

Notary Public.



My commission expires: March 16, 1987

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1983
9-30-83
CONSERVATION DIVISION
Wichita, Kansas