

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15,135,21870-0000

LEASE NAME Ryersee C

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

3630 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 35 TWP. 18 RGE. 21 (E) or (W)

LEASE OPERATOR John Jay Darrah, Jr.

COUNTY Ness

ADDRESS 412 E. Douglas, #1; Wichita, KS 67202

Date Well Completed 9-8-80

PHONE#(316) 263-2243 OPERATORS LICENSE NO. 5088

Plugging Commenced 11/20/89

Character of Well SWD

Plugging Completed 11/20/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/20/89 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? filed w/original SWD App.

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4190

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				5-1/2	set at 1338';	FBTD 1300'
					Perfs at 772-800,	824-866, 900-950'
					No casing recovering;	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 1st plug pumped 400 bls. hulls and 75 sx cement down 5-1/2'; max pressure 450 psi & shut in 300 psi. 2nd plug pumped 100 sx cement down 8-5/8" x 5-1/2" annulus, Max pressure 450 psi & shut in 300 psi; used 65/35 Pozmix 8% gel by Halliburton

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License # 5287

Address Box 405, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John Jay Darrah, Jr.

STATE OF Kansas COUNTY OF Sedgwick, ss. CONSERVATION DIVISION
Wichita, Kansas

John Jay Darrah, Jr.

(Employee or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) John Jay Darrah, Jr.
412 E. Douglas, Suite One



SWORN TO before me this 18th day of December, 19 89

My Commission Expires: 10/13/93

[Signature]
 Dorene K. Dunn Public

THUNDERBIRD DRILLING, INC.
BOX 97
ELLINWOOD, KANSAS 67526

15-135-21870-0000

COMPLETION REPORT

RYERSEE #1 SWD

- 9-4-80 Moved in cable tools and rigged up.
- 9-5-80 Petro-Log ran G/R log from T.D. @ 1300' up to 400'.
Perforated Cedar Hills 1 per foot . Following intervals:
900' to 950'
824' to 866'
772' to 800'
Swabbed into pits. Carrying 50 % red sand. Started flowing.
Flowing full 2" stream. Flowed all working pits full.
Cleaned up. S.I.P. 26#.
- 9-6-80 30 # S.I.P. Flowed pits full again. Carried 10 % red sand
at start. Then cleared up.
- 9-7-80 Shut down - Sunday.
- 9-8-80 S.I.P. 30 #. Ran 15 joints 2 3/8" duo-lined tubing plus
8 joints new 2 3/8" w/TK75 coating with coated Arrow
model "H" tension packer. Set packer @ 717.05'. Well
flowed continuously. Shut in. Tore down cable tools
and moved off location.

RECEIVED
STATE OF KANSAS COMMISSION

10/17/80

CONSERVATION DIVISION
Wichita, Kansas

15135-21870 0000

THUNDERBIRD DRILLING, INC.

PIPE RECORD

DATE August 26, 1980 County Ness

LEASE Ryersee WELL NO. #1 SWD

SEC 35 TWS. 18 S RG. 21 W

LOCATION NW-SE-SE ELEVATIONS 2111

TOTAL DEPTH 4190 ZERO POINT ABOVE B H

PIPE SET @ 1338.20 PIPE SIZE 5 1/2 14#

SHOE JOINT 32.94 FLOAT 1305.26

CENTRILIZERS @ Basket @ 1336 - 1305 - 1174 - 702

SCRATHERS @

CEMENT SACKS USED 325 50-50 posmix w/6 % gel.

TOP OF PRODUCING FORMATIONS

ARBUCKLE

SIMPSON

LANSING

MARMATION

OTHER Cedar Hills @ 751

COMPLETION RECORD

PERFORATIONS 772 to 800 824 to 866 900 to 950

OPEN HOLE PLUG BACK 1300

HCURLY SWAB 70 +

ACID GALLONS DATE TREATED

SAND FRAC

REMARKS Cement circulated. Drilled by Vincent Oil as dry hole
(Slawson) Rig, turned over to Thunderbird @ 9 P.M. 8-25-80 to run
casing as SWD

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1980
CONSERVATION DIVISION
Wichita, Kansas