

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Location as "NE/CNWSW" or footage from lines Ness County, Sec. 35 Twp. 18 Rge. 21 (E) (WX)
C/NE/SW
Lease Owner Braden Drlg., Inc.
Lease Name Mellick Well No. E "A"
Office Address 1620 Wichita Plaza Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12-14-71 _____ 19____
Plugging completed 12-20-71 _____ 19____
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1230 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	250	None
				5 1/2	4226	3138.31'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured T.D. to 4220'. Dumped 25 ft. sand and 5 sacks cement on bottom.
Shot casing at 3219.3120 ft. Pulled a total of 101 joints of 5 1/2" casing.
Halliburton squeezed with 3 sacks hulls, 25 sacks gel and 120 sacks 50/50
pozmix with 6 % added gel.


RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Engineering, Inc.
Address Box 698 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
Box 698 Great Bend, Kansas 67530
(Address)


CATHY MILLER
NOTARY PUBLIC
Barton County, Ks.

SUBSCRIBED AND SWORN to before me this 20th day of December, 1971

Cathy Miller
Cathy Miller Notary Public.

My commission expires September 30, 1975

DRILLER'S LOG

COMPANY: Braden Drilling, Inc., 1620 Wichita Plaza Bldg., Wichita, Kansas 67202

CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202

LEASE: #1 Mellick "A"

LOCATION: C NE SW (150' SW) 35-18S-21W, Ness County, Kansas

COMMENCED: December 26, 1969

COMPLETED: January 11, 1970

CASING: Set 8 5/8" Surface Casing @ 250'/160 sacks cement
Set 5 1/2" Casing @ 4226'/200 sacks cement

0-250	Post Rock & Shale
250-465	Shale & Sand & Red Bed
465-790	Red Bed
790-1050	Sand
1050-1365	Red Bed & Shale
1365-1404	Anhydrite
1404-1645	Shale
1645-1716	Salt Section
1716-1840	Shale & Red Bed
1840-1915	Shale
1915-2090	Shale & Lime Streaks
2090-3537	Lime & Shale
3537-3650	Shale & Lime
3650-3813	Lime
3813-3865	K. C. Lime
3865-3951	Lime
3951-4035	Lime & Shale
4035-4105	Lime
4105-4177	Lime
4177-4192	Cherokee Sand
4192-4200	Lime
4200-4226	Sand & Cong.
4226-4230	Miss.
4230	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1971
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Mellick "A", located in C NE SW (150' SW) 35-18S-21W, Ness County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 14th day of January, 1970.

My Commission Expires:
March 25, 1972.

Catherine Darcey
Notary Public - Catherine Darcey

