

509

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,961-0000

LEASE NAME June Donovan

WELL NUMBER 2-23

SPOT LOCATION S/2-NW-NE/4

SEC. 23 TWP. 32 RGE. 11 (X) or (W)

COUNTY Barber

Date Well Completed 12/8/84

Plugging Commenced 6/15/85

Plugging Completed 10/22/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KBW Oil & Gas Company

ADDRESS 3632 N.W. 51st St., Suite 205, Okla. City, OK 73112

PHONE (405) 947-1238 OPERATORS LICENSE NO. 5993

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? _____

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed? yes if not, is well log attached? _____

Producing formation Indian Cave (Admire) Depth to top 2558' bottom 2591' T.O. 2635'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Indian Cave (Admire)</u>	<u>Gas & saltwater</u>	<u>2558</u>	<u>2591</u>	<u>8 5/8</u> <u>4 1/2</u>	<u>233</u> <u>2633</u>	<u>None</u> <u>2172</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plug back 2599, sand from 2599 to 2509 4sx cement from 2509 to 2480, 3sx hulls, 10 sx jell, 50sx cement, 10sx jell 1sx hulls 8 5/8 plug, 100sx cement, 60-40 POZ 6% jell - Sun pumped

Paul Luthie and Elmo Morgenstern on location.
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp. License No. 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct so help me God.

(Signature) *Elmo Morgenstern*
(Address) Medicine Lodge, KS 67104

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 30 day of October, 1985

Pamela Ricke
Notary Public

NOV 1 1985
11-1-85
CONSERVATION DIVISION
Wichita, Kansas
My Commission expires: 10-11-87

PAMELA RIGKE
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 10-11-87

Form CP-4 /-84
Revised 06-83