

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21,756-0000

LEASE NAME June Donovan

WELL NUMBER 1-23

SPOT LOCATION NE-NE-NE

SEC. 23 TWP. 32 RGE. 11 ~~W~~ (W)

COUNTY Barber

Date Well Completed 1/28/84

Plugging Commenced 1/3/86

Plugging Completed 1/9/86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR KBW Oil & Gas Co.

ADDRESS 3632 N.W. 51st St., Suite 205, Oklahoma City, OK 73112

PHONE # (405) 947-1238 OPERATORS LICENSE NO. 5993

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Toronto (Douglas) Depth to top 3627 bottom 3663

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
Indian Cave (Admire)	gas & water	2584	2616	8 5/8	267	None
Toronto (Douglas)	oil & water	3627	3663	5 1/2	3709	2074

RECEIVED  
STATE CORPORATION COMMISSION  
1-14-86  
IAN 14 1986  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plug back 3683, sand from 3683 to 3580, 4sx cement from 3580 to 3560, spot 3sx hull, 10sx jell, 50sx cement, 5sx jell, 1sx hull, plug, 100sx cement, 2% cc, 60-40 POZ, 6% Jell (B J Hughes pumping)

Jack Luthie and E. Morgenstern on location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp. License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Elmo Morgenstern

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 10 day of January, 1986

Caren J. Winchell  
Notary Public

My Commission expires: June 29, 1987