

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Harper County, Sec. 17 Twp. 33S Rge. 9 (W)

Location as "NE/CNWxSWx" or footage from lines SW SE SE

Lease Owner K & E DRILLING, INC.

Lease Name Crisfield Townsite Well No. #1

Office Address 1006 Central Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 7-14-54 19

Application for plugging filed 7-14-54 19

Application for plugging approved 7-14-54 19

Plugging commenced 8:00 a. m. 7-14-54 19

Plugging completed 8:00 p. m. 7-14-54 19

Reason for abandonment of well or producing formation 11

Commercial quantity of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4855 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8		none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 261'. Set plug at 261' topped with 15 sacks cement. Filled to 20' with heavy mud, second plug at 20' capped with five sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 29 1954  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E Drilling, Inc.  
Address 1006 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Dale Silcott, Sec'y - Treas.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott

1006 Central Bldg.  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 54

Francis Walker  
Notary Public.

My commission expires June 25, 1956

PLUGGING  
FILE SEC 17 T 33 R 9W  
BOOK PAGE 2 LINE 38

K & E DRILLING, INC.  
CHRIS FELD TOWNSITE #1

SW SE SE Sec. 17-33S-9W  
Harper County, Kansas

Casing

Cement

8 5/8" Set @ 195'

135 Sacks

FORMATION

DEPTH

Red rock, hard	0 - 350
Intermittent streaks red rock, grey shale	350 - 635
Anhydrite	635 - 665
Shale	665 - 1165
Salt and Shells	1165 - 1380
Lime and shale	1380 - 1550
Lime	1550 - 1735
Flaky Shale with streaks of lime	1735 - 1805
Lime & shale	1805 - 1845
Shale	1845 - 1875
Lime	1875 - 1885
Lime & shale	1885 - 1990
Shale & lime	1990 - 2155
Lime & shale	2155 - 2240
Shale w/ streaks of lime	2240 - 2495
Lime & shale	2495 - 2700
Shale & broken lime	2700 - 2790
Lime & shale	2790 - 2875
Shale and a little lime	2875 - 3032
Shale	3032 - 3064
Lime & shale	3064 - 3180
Sand, lime & shale	3180 - 3227
Lime & shale	3227 - 3272
Sand	3272 - 3324
Shale	3324 - 3397
Sandy lime & shale	3397 - 3468
Sand	3468 - 3523
Shale streaks of sand	3523 - 3588
Shale & sandy lime	3588 - 3673
Lime & shale	3673 - 3737
Sand	3737 - 3853
Broken Lime	3853 - 3861
Shale & lime	3861 - 3897
Shale	3897 - 4006
Lime	4006 - 4176
Lime & shale	4176 - 4470
Mississippi	4470 - 4539
Mississippi chert & chert	4539 - 4560
Dolemite w/ streaks of chert	4560 - 4600
Lime & shale	4600 - 4709
Shale	4709 - 4728
Shale & lime	4728 - 4746
Lime	4746 - 4792
Lime & shale	4792 - 4806
Simpson Sand	4806 - 4855

Comm: 6-21-54  
Comp: 7-14-54  
Total Depth: 4855

STATE OF KANSAS )  
                          ) SS  
SEDGWICK COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.

*Robert A. Smith*

Subscribed and sworn to before me this 28th day of July, 1954

My Commission Expires

*Francis Mader*  
Notary Public

*June 25, 1956*

PLUGGING  
SW SE 12 33 S 9 W  
HARPER COUNTY, KANSAS

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 28 1954  
CONSERVATION