

15-063-00222-0000

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Gove County. Sec. 33 Twp. 15S Rge. 26 (R)XXXX(W)

Location as "NE/CNW%SW%" or footage from lines C SE SE

Lease Owner Empire Drilling Company

Lease Name Babcock Well No. 1

Office Address 650 Fourth Natl. Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 24 1963

Application for plugging filed March 24 1963

Application for plugging approved March 24 1963


Plugging commenced March 24 1963

Plugging completed March 24 1963

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4592 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface-Shale	0	219'	8 5/8"	197'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Plug set at 660' with 20 sacks cement.
- Plug set at 180' with 20 sacks cement.
- Plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 4 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company

Address 650 Fourth Natl. Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Dan J. Kornfeld (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 Fourth National Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 1963

Lucille H. Harr
Lucille H. Harr Notary Public.

My commission expires October 21, 1966



L O G

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Babcock #1
 LOCATION: C SE SE Section 33-15S-26W, Gove County, Kansas

COMMENCED: March 5, 1963
 COMPLETED: March 24, 1963
 ELEVATION: 2583 KB
 POTENTIAL: D & A

0	to	219	Surface Shale
219	to	420	Shale
420	to	1200	Clay & Shale w/ Shells
1200	to	1700	Shale & Shells - Sand
1700	to	1996	Sand & Shale
1996	to	2033	Anhydrite
2033	to	2522	Shale & Shells
2522	to	3245	Lime & Shale
3245	to	3315	Lime
3315	to	3740	Lime & Shale
3740	to	3780	Lime & Chert
3780	to	3800	Lime
3800	to	3870	Lime & Shale
3870	to	3915	Lime
3915	to	3943	Lime & Chert
3943	to	3975	Lime
3975	to	3995	Lime & Shale
3995	to	4025	Lime
4025	to	4035	Lime & Chert
4035	to	4095	Lime & Shale
4095	to	4150	Lime
4150	to	4280	Lime & Shale
4280	to	4335	Lime
4335	to	4440	Lime & Shale
4440	to	4490	Lime Shale & Chert
4490	to	4580	Lime & Chert
4580	to	4591	Chert
4591			Rotary Total Depth

SET: 197' of 8 5/8" with 135 sacks cement

SCHLUMBERGER ELECTRIC LOG TOPS:

Waubensee	3431	-848
Queen Hill	3704	-1121
Heebner	3838	-1255
Toronto	3858	-1275
Lansing	3879	-1296
Base Kansas City	4176	-1593
Pawnee	4324	-1741
Fort Scott	4384	-1801
Cherokee Group	4410	-1827
Base of Pennsylvanian		
Conglomerate	4458	-1875
Mississippian (Spergen)	4477	-1894
Mississippian (Warsaw)	4529	-1946
Log Total Depth	4592	

RECEIVED
STATE CORPORATION COMMISSION

APR 4 1963

CONSERVATION DIVISION
Wichita, Kansas

C E R T I F I C A T I O N

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Babcock #1, C SE SE Section 33-15S-26W, Gove County, Kansas, as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld
Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 2nd day of April, 1963.

My commission expires October 21, 1966.

Lucille H. Harr
Lucille H. Harr, Notary Public