

15-115-20178-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Marion County. Sec. 17 Twp. 17 Rge. 4 E E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C SE SW

Lease Owner Slusser Drilling Co.  
Lease Name Shields Well No. 3  
Office Address P.O.Box 275 Marion Kansas 66861 SWD  
Character of Well (Completed as Oil, Gas or Dry Hole) OIL  
ANSWER



Locate well correctly on above  
Section Plat

Date Well completed 8-3 1972  
Application for plugging filed 5-20 1978  
Application for plugging approved 5-21 1978  
Plugging commenced 6-18 1978  
Plugging completed 7-18 1978  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Hickey  
Producing formation Depth to top Bottom Total Depth of Well 2685'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2240'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set. Plugged off bottom of hole with sand. Sand  
from 2685' to 2600'. Dumped 5 sx of cement.  
Mudded hole to 225'. Made rock bridge. Dumped  
16 sx cement. Mudded hole to 40'. Dumped 9 sx  
cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 21 1978

CONS. DIV.  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Inc.  
2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno, ss.

Art Lamb (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 King St. Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 1978

Judy Lamb  
Notary Public.

My commission expires April 18, 1982

DRILLERS LOG

Company	Slusser Drilling Company	Commenced 8/8/72
Contractor	Slusser Drilling Company	Completed 8/13/72
Farms	Shields #3	C SE SW 17-17-4E
8 5/8	@ 206	Marion County, Kansas
5 1/2	@ 2634	

*125 ref*  
*100 ref*

Surface soil	5
Shale and lime	85
Lime and shale	715
Shale and lime	1050
Shale and shells	1230
Lime and shale	1380
Shale and lime	1520
Sand, shale & lime	1550
Lime and shale	1626
Shale	1690
Sand and shale	1753
Lime	1769
Shale	1784
Lime	1793
Shale	1807
Lime	2190
Lime and shale	2336
Conglomerate	2373
Chat	2444
Lime	2472
Shale	2630
Lime	2685 Rotary T.D.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 05 1977

CONSERVATION DIVISION  
Wichita, Kansas