

Well Plugging Record

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

K.A.R. -82-3-117

API NUMBER 15-077-21,395 -00-00
LEASE NAME Prouse L
WELL NUMBER 1-35

TYPE OR PRINT
NOTICE: Fill out completely and return to Cons. Div. office within 30 days.
660 Ft. from South Line of Section
4620 Ft. from East Line of Section

LEASE OPERATOR McCoy Petroleum Corporation
ADDRESS P. O. Box 780208
CITY, STATE, ZIP Wichita, Kansas 67278-0208
PHONE # 316-636-2737
Character of Well Oil
SPOT LOCATION N2 SW SW
Section 35 Township 33 Range 8 W
County Harper
Date Well Completed 5/7/01
Date Plugging Commenced 8/19/02
Date Plugging Completed 8/20/02

The plugging proposal was approved on 8/19/02 (date)
by Doug Louis (KCC District Agent's Name)
Is ACO-1 Filed? yes If not, is well log attached?
Producing Formation(s) Miss. Depth to Top 4656 Bottom 4664 T.D. 4739
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULL OUT. Row 1: 8-5/8", 263, 0. Row 2: 5-1/2", 4737, 3430.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sand at 4598', bailed 5 sacks cement. Shot pipe 3508, 3430', worked free. Pull to 1350', pump 35 sacks cement. Pull to 900', pump plug, it flowed back. Pump 80 bbls mud, pump 35 sacks cement. Pull to 310', circulate cement to surface w/95 sacks cement. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc.
Licence No. 31925
Address 401 W. Main City: Lyons State: KS Zip 67554
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)

STATE OF KANSAS COUNTY OF Sedgwick, ss.

Scott Hampel (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.


(Signature) X [Signature of Scott Hampel]
(SCOTT HAMPSEL, Petroleum Engineer)

(Address) 453 S. Webb, Suite 310, P.O. Box 780208 City: Wichita State: KS Zip 67278

SUBSCRIBED AND SWORN TO me this 9 day of September, 20 02

My Commission Expires: 9/5/2006

X [Signature of Karen E. Houseberg]
Karen E. Houseberg (Notary Public)



Form CP-4
Revised 12-92

OR