

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-20,868-00-00

LEASE NAME Morrow

WELL NUMBER 1-34

 Ft. from S Section L

 Ft. from E Section L

SEC. 34 TWP. 33 RGE. 8 ~~XX~~ W

COUNTY Harper

Date Well Completed 6-2-83

Plugging Commenced 10-21-92

Plugging Completed 5:15 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Great Bend Casing Pullers, Inc.

ADDRESS P.O. Box 251, Great Bend, Kansas 67530

PHONE# (316) 793-9711 OPERATORS LICENSE NO. 4635

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-21-92 (date)

by Steve Van Geison (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Miss Depth to Top 4666 Bottom 4670 T.D. 4750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	310	0
				4 1/2	4746	3200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from feet to feet each.
Bottom plug: Sanded to 4600 ft & bailed 4 sx cement.

Top plug: Pulled pipe to 1400 & displaced 35 sx cement (60/40 with 2% gel). Pulled pipe to 950 & spotted 35 sx cement. Pulled pipe to 350 & circulated to surface with 105 sx cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Bend Casing Pullers, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Gary G. Burke (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct, so help me God.

(Signature) Gary G. Burke RECEIVED

(Address) Box 251, Great Bend, Kansas STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 22 day of October, 1992



Anna K. Burke CONSERVATION DIVISION
Notary Public Wichita, Kansas

My Commission Expires: 4-30-96