


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Meade County, Sec. 3 Twp. 37S Rge. 29(W)

Location as "NE/CNW%SW%" or footage from lines NE NE NE
Lease Owner Texaco Inc.
Lease Name W. F. Wilson Well No. 1
Office Address 614 Bitting Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 2-22-1958
Application for plugging filed (Revised) 3-12-1969
Application for plugging approved 2-7-1969
Plugging commenced 3-26-1969
Plugging completed 3-29-1969
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 1-20-1968
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves
Producing formation Marmaton Depth to top 5242 Bottom 5250 Total Depth of Well 5890 Feet
Show depth and thickness of all water, oil and gas formations. 5737 PBTB

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|------|---------|--------|------------|
| Marmaton | Oil | 5242 | 5250 | 16" | 35' | None |
| Morrow | Oil | 5722 | 5735 | 10-3/4" | 1519' | None |
| | | | | 7" | 5890' | 2844' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: 5737-5100 w/50 sxs cmt.
5100-900 w/hvy mud
900-800 w/40 sxs cmt.
800-30 w/hvy mud
30-surf w/10 sxs cmt.

Complete 12 Noon 3-29-69.

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling, Inc.
Address Box 506, Liberal, Kansas 67901


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
M. R. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. R. Wilson
614 Bitting Building, Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 28th day of April, 1969

Peggy Sue Jones
Notary Public.

My commission expires 10-13-69



DRILLING LOG

The Texas Company - W. F. Wilson No. 1 Well, Sec. 3, Twp 34 S.,
Rge 29 W., Meade County, Kansas.

Started: 1-17-58
Completed: 2- 9-58
Casing: Set 10 3/4" at 1519' W/800 Sax Pozmix at
4:00 PM 1-19-58. W O C & Cement outside
W/ 1" - 40 Hours
Set 7" at 5890' W/125 Sax at 8:00 AM 2-9-58

0 - 476 Sand & Red Beds
476 - 790 Shale & Red Beds
790 - 1519 Red beds & shale
1519 - 2047 Shale & sand
2047 - 2397 Shale
2397 - 2517 Lime & shale
2517 - 2790 Shale & Lime
2790 - 2905 Lime & shale
2905 - 3620 Shale & lime
3620 - 3738 Lime & shale
3738 - 3907 Lime & shale W/Dolomite
3907 - 4212 Lime & shale
4212 - 4396 Shale, sand & lime
4396 - 4428 Shale & Lime
4428 - 5161 Lime & shale
5161 - 5172 Lime
5172 - 5207 (Cored)
5207 - 5247 Lime & shale
5247 - 5307 (Cored)
5307 - 5334 Lime
5334 - 5393 Lime & shale
5393 - 5421 Lime
5421 - 5546 Lime & shale
5546 - 5735 Lime
5735 - 5890 T.D. Lime & shale

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1969
CONSERVATION DIVISION
Wichita, Kansas