

JAN 28 1983

15-119-20561-00-00

Form CP-4  
Rev. 12-15-80

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Meade SEC. 3 TWP. 34S RGE. 27 E/W  
Location as in quarters or footage from lines:  
NE SW NE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Service Drilling  
Lease Name Carol Well No. #1-3  
Office Address 1800 4th National Bldg., Tulsa, OK 74119  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 1-14-83  
Plugging completed 1-21-83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Paul Luthi  
Producing formation Marmaton Depth to top 5276 bottom 5286 T.D. 5370'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Lansing Kansas City	Salt Water	4508	5026	8 5/8"	1561'	None
Marmaton	Oil & Water	5038	5370	4 1/2"		2421'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

1-14, Pumped 25 sks. cem. to 5200'. 1-17, Shot pipe @ 3017', @ 2708', @ 2421'.  
1-19, Pumped 25 sks. cem. to 2421', Pumped 70 sks. cem. to 1610', Pumped 40 sks.  
cem. to 750'. 1-20 Capped w/10 sks. cem. from 33'-3'. Welded on steel plate  
w/name & date using 9.5 lbs. 38 visc. mud between plugs.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mike Proctor's Casing Pullers, Inc.  
3022 NW Expwy, #305, Okla. City, OK 73112

STATE OF Oklahoma COUNTY OF Tulsa, ss.  
Mark Pulver (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Mark L. Pulver  
1800 4th Nat'l. Bank, Tulsa, OK 74119  
(Address)

SUBSCRIBED AND SWORN TO before me this 15<sup>th</sup> day of February, 19 83  
Camela A. Lancaster  
Notary Public.  
My Commission expires: April 28, 1985



2-4-83  
FEB 4 1983