

API NUMBER 15135-30246-0000
 None

LEASE NAME Borger

WELL NUMBER 4

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 25 TWP. 19S RGE. 22 (W)

COUNTY Ness

Date Well Completed 7-19-66

Plugging Commenced 5-10-88

Plugging Completed 5-18-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P.O. Box 21468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568 74121

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on N/A (date)

by N/A (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, Is well log attached? ----

Producing Formation Osage Depth to Top 4394 Bottom 4403 T.D. 4403

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Osage	Oil	4394	4403	8 5/8	429	-0-
				5 1/2	4394	1978

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand and 5 sacks cement to 4300'. Shot pipe @ 2550', 2215', 1978', pulled a total of 64 joints of 5 1/2" casing. Plugged surface with 4 hulls, 10 gel, 60 cement, 10 gel, 1 hull, 150 cement 60/40 pos, 6% gel.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347, Chase, KS. 67524

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P.O. Box 21468

SUBSCRIBED AND SWORN TO before me this 2 day of June, 19 88

X Brenda Bowles
 Notary Public

My Commission Expires: 6-27-90

