

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-10043-00-00
Spot: N2S2NWNE Sec/Twnshp/Rge: 19-22S-34W
4479 feet from S Section Line, 1978 feet from E Section Line
Lease Name: A C MADDUX Well #: 1
County: FINNEY Total Vertical Depth: 4862 feet

Operator License No.: 32606
Op Name: DEVON ENERGY PRODUCTION COMP
Address: 333 W SHERIDAN AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2000		
PROD	5.5	4845	0	WITH 175 SX CMT
SURF	8.625	833		WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2013 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GLEN SMITH Company: DEVON ENERGY Phone: (806) 323-1245

Proposed Plugging Method: SET CIBP @ 3750' WITH 2 SX CMT. PLUG AT 1950' WITH 15 SX GEL & 50 SX CMT. PLUG AT 860' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2013 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CMT RETAINER @ 4050' WITH 25 SX CMT OVER PERFS 4770-4774'. TBG STUCK IN LINER. PUMP 90 SX CMT WITH 150# HULLS IN THE LAST 50 SX CMT TO 4000' VIA TBG. MAXIMUM PRESSURE 1200#. SHOOT TBG OFF AT 2026'. LEFT 19 JOINTS IN THE HOLE. SET CIBP @ 2000'. TEST CASING TO 750#. HOLDING. RUN BOND LOG FROM 1400' TO 800' TO DETERMINE EXTENT OF CMT SQUEEZE JOB DONE THROUGH CASING LEAKS FROM 986' TO 1008' IN 2/1982. FOUND BOTTOM OF CMT AT 1240' & TOP OF CMT AT 986'. PERFORATE AT 1950'. INJECTION RATE 3 BPM @ 50#. PUMP 50 SX CMT THROUGH PERFS WITH 100# HULLS IN LAST 25 SX. PERFORATE AT 850'. INJECTION RATE 3 BPM @ 500#. PUMP 180 SX CMT DOWN 5 1/2" CASING (60 SX CMT OUTSIDE PERFS). HAD BLOW ON ANNULUS BUT NO FLUID TO SURFACE. PUMP 30 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. PRESSURE TO 500#. HOLDING. 9/27/13: TAG TOC INSIDE 5 1/2" CASING AT 560'. FILL TO 0' WITH 2 YARDS REDIMIX. ANNULUS FULL OF CMT FROM PREVIOUS DAY.

Perfs:

Top	Bot	Thru	Comments
3900	4000		
3800	3806		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

[Handwritten Signature]
10/25/13

(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

RECEIVED
OCT -7 2013
KCC DODGE CITY

OCT 10 2013

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

[Handwritten Initials]