

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20572-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 19-22S-34W  
2996 feet from S Section Line, 1669 feet from E Section Line  
Lease Name: MADDUX A C Well #: 3-19  
County: FINNEY Total Vertical Depth: 4225 feet

Operator License No.: 32606  
Op Name: DEVON ENERGY PRODUCTION COMP  
Address: 333 W SHERIDAN AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3754		WITH 2 SX CMT
PROD	5.5	4223	0	WITH 300 SX CMT
SURF	8.625	864		WITH 350 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/23/2013 8:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: GLEN SMITH Company: DEVON ENERGY Phone: (806) 323-1245

Proposed Plugging Method: SET CIBP @ 3750' WITH 2 SX CMT. PLUG AT 1950' WITH 15 SX GEL & 50 SX CMT. PLUG AT 900' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 09/24/2013 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 3754' WITH 2 SX CMT. 9/23/13: ATTEMPT TO LOAD & TEST CASING. COULD NOT. CASING & ANNULUS ON VACUUM. PERFORATE AT 1950'. SET CMT RETAINER AT 1840'. RUN TBG & STING INTO RETAINER. INJECTION RATE 2 BPM @ 100# CIRCULATING OUT 5 1/2" CASING THROUGH HOLES ABOVE RETAINER. DROP STANDING VALVE & TEST TBG TO 1000#. PUMP 50 SX CMT THROUGH PERFS & STING OUT OF RETAINER. HAD FULL CIRCULATION OUT 5 1/2" CASING. NO BLOW ON 5 1/2" X 8 5/8" ANNULUS. PERFORATE @ 1000. INJECTION RATE DOWN 5 1/2" CASING 3 BPM @ 50#. START TO PUMP CMT AND IMMEDIATELY GOT CMT OUT ANNULUS. MORE HOLES IN 5 1/2" CASING. RAN 120' OF TBG & CIRCULATED OUT CMT. SDON. 9/24/13: TAG TOC IN 5 1/2" AT 1280'. SET CMT RETAINER @ 910'. ESTABLISH INJECTION RATE. CIRCULATING UP 5 1/2" CASING THROUGH HOLES ABOVE RETAINER. NO CIRCULATION OR BLOW UP 8 5/8" ANNULUS. CLOSE 5 1/2" CASING VALVE & ATTEMPT TO CIRCULATE UP 8 5/8" ANNULUS @ 1000#. COULD NOT. CIRCULATE 5 1/2" CASING FULL OF CMT THROUGH HOLES IN 5 1/2" ABOVE RETAINER WHILE STUNG IN TO RETAINER USING 100 SX CMT. CLOSE 5 1/2" VALVE & ATTEMPT BRADEN HEAD SQUEEZE INTO 8 5/8" @ 1000#. COULD NOT ESTABLISH RATE. PUMP 170 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS @ 300#. TOOH WITH TBG. TOP OFF 5 1/2" X 8 5/8" WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3900	3904		
3804	3811		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
10/25/13

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

RECEIVED  
OCT -7 2013  
KCC DODGE CITY

OCT 10 2013

CONSERVATION DIVISION  
WICHITA, KS