

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22897-00-00
Spot: NWSESW Sec/Twnshp/Rge: 17-8S-17W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: LESLIE WELLS Well #: 3
County: ROOKS Total Vertical Depth: 3399 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3399		150 SX
SURF	8.625	242		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/18/2013 11:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL Phone: (785) 259-1928

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Squeezed at 2084' - 2116' w/200 sx cement.
Perforations: 3132' - 3292.5

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/18/2013 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 790' and 1300'.
Ran tubing to 2850' and pumped 125 sx cement w/200 # hulls.
Pulled tubing to 1900' and pumped 125 sx cement w/200 # hulls.
Pulled tubing to 950' and pumped 100 sx cement w/100 # hulls to circulate cement to surface.
Pulled all tubing. Topped off 5 1/2" casing w/10 sx cement.
Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 300 psi.

GPS: 39.35268 N -099.24494W

Perfs:

Top	Bot	Thru	Comments
3360	3368		
3291	3294		
3252	3272		
3172	3193		
3094	3133		

Remarks: ALLIED TICKET # 54867

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

10/25/13

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

SEP 25 2013

OCT 09 2013

CONSERVATION DIVISION
WICHITA, KS